



ESTIMATE

Tidewater Home Improvement LLC
Class B Contractor #2705172863
414 Worster Ave
Hampton, Virginia 23669
United States

(757) 551-6413
tidehomepro.com

BILL TO

Rebecca Thompson
Rebecca Thompson
1068 Rittman Rd
Virginia Beach, VA 23464
United States

rebecca.thompson07@yahoo.com

Estimate Number: 1398
Estimate Date: September 16, 2026
Valid Until: September 23, 2026

Grand Total (USD): \$3,150.00

Clean Up & Debris Removal	1
Clean out the crawlspace and remove all of the existing vapor barrier.	
10mil White Vapor Barrier	1
Install brand new 10 mil white vapor barrier.	
Third party to spray a DSV treatment	1
DSV treatment (disinfectant, sanitize and virucide) by a third-party pest control company.	
Air Seal gaps and holes with foam and wire steel curtain	1
Interior crawlspace rodent foam air seal - seal any visible rodent entry points in the foundation perimeter walls from the inside, as well as the air-conditioning area and vent area on the interior of the crawlspace.	

Grand Total (USD): **\$3,150.00**

Notes / Terms

SCOPE OF WORK

Clean Up & Debris Removal: remove ground debris and all of the existing vapor barrier from the crawlspace and away from home; grade crawlspace, lift cables off the ground, secure ductwork to joist with straps and off the floor when possible (1,571 sq ft).

Sanitization: DSV treatment (disinfectant, sanitize and virucide) performed by a third-party pest control company on the ground - applied after the existing vapor barrier has been removed and before the new 10 mil white vapor barrier is installed.

10 MIL Vapor Barrier: measure on-site and install 10 mil white vapor barrier with pier overlap and secured with crawlspace staples or wire pins (1,571 sq ft).

Rodent Exclusion: interior crawlspace rodent foam air seal - seal any visible rodent entry points in the foundation perimeter walls from the inside, as well as the air-conditioning area and vent area on the interior of the crawlspace.

NOT INCLUDED: insulation; crawlspace door; general conditions; permits.

Notes:

**Jobsite will be left clean once completed.



Warranty:

**12 months workmanship on the project.

Payment Terms:

Total Project Cost: \$3,150.00

Deposit to Schedule: \$1,575.00

Final Payment: \$1,575.00

Check is a preferred method.

**You can pay by credit card using the link below.

<https://request.plastiq.com/pay-tidewater-home-improvement-llc>

Cards not eligible for payment:

- Virtual Affirm credit card

Validity: valid until September 23, 2026.



Crawlspace Clean Out, Vapor Barrier & Rodent Exclusion - 1068 Rittman Rd, Virginia Beach, VA 23464